

River Street Pump Station Upgrade

Dover, NH

August 2021

John Storer, Director of Community Services
Tim Vadney, PE, Wright-Pierce



Presentation Overview

Introduction
Proposed Funding
Station Condition & Concerns
Previous Projects & Planning
Facility Plan
Proposed Upgrade
Schedule
Next Steps



- **2020 General Permit**
 - No upgrades required at WWTF due to stability of existing processes
- **Shift Focus on next highest priority**
 - Waterfront development
 - Increased public presence
 - Address odor and reliability

Funding



- **Capital Improvement Plan (CIP)**
 - Current budget includes \$1M for Odor Control Upgrades
 - Ongoing meetings with Cathartes
- **Proposed CWSRF Funding**
 - \$7.2 Loan
 - > \$900K in Principal Forgiveness

River Street Pumping Station





- Constructed in 1991
 - Allowed for relocation of WWTF to its current location
 - Serves as headworks for 80% of City's flow to WWTF
- The River Street Pump Station is the **City's largest wastewater pumping station**
- Conveys flows up to 17 MGD to the WWTF
 - Dry & Wet Weather Flow Pumping
 - Influent Screening & Grit Removal

River Street Pumping Station

Most of the building systems, control systems, and electrical gear are **outdated and beyond their useful life**

In 2018, a VFD failed due to fire incident. In 2019, VFDs were replaced and will be reused as part of upgrade





Why Upgrade Now?

1

Address aged equipment and ancillary systems for this critical station


2

2020 Facility Plan indicated select areas of the station are in poor condition

3

Address odor concerns ahead of waterfront development

Reliability Concerns



- Force Main
 - Single, 36-inch prestressed concrete pipe
 - ~ 3-mile
 - 30 years old
 - Biggest **redundancy** and **emergency response** concern
- Development of bypass plan
- Consideration of overflow tank



City of Dover Wastewater Experience



WWTF Upgrades

- 2014 Upgrade & MLE conversion
- 2021 Cleanings Facility Upgrade



Pump Station and Force Main Upgrades


- 2007 Varney Brook PS Force Main Replacement
- 2007 River St PS Master Plan
- 2010 River St PS Upgrade
- 2019 River St PS VFD Replacement
- 2020/2021 Varney Brook PS Upgrade



Collection System I/I Initiatives

- Manhole inspections, CCTV, Dye and Smoke Testing
- Infiltration/Inflow evaluation & mitigation
- Roof Leader Investigations
- Sewer replacement

Previous River Street Pump Station Work



2007 Master Plan



2010 Upgrade

- New Influent Screening;
- Grit Removal;
- Chemical Feed;
- Dry Weather Pumping
- Construction of sodium hypo chemical storage and garage



2019 VFD Replacement

- Replaced existing pump variable frequency drives (VFD) in kind



2021 Facility Plan


- Condition Assessment
- Conceptual Design
- Recommended improvement projects for future upgrade

River Street Pump Station Facility Plan

- River Street Pump Station - next highest priority for City
 - Performed comprehensive pump station evaluation
 - Prepared recommendations for select building upgrades
 - Review of process systems for current and future conditions
 - Framed the **blueprint** for next upgrade




Architectural/
Structural



Mechanical/
Plumbing



Electrical/
Instrumentation



Civil-Site Work



Process



SCADA
Integration


Odor Control Mitigation




- Surrounding area to be developed - **Cathartes**
- Sludge Garage is source of significant odor production
- **Odor Control = High Priority!**

Odor Control

- **Activated Carbon Units**
- **Reliable performance**
- **Low capital and maintenance costs**
- **Easy operation**



Sludge Garage



*Conceptual Design

Sequence of Work

- Consideration given to initial Odor Control Upgrades
 - Requires additional planning for integration of:
 - HVAC
 - Electrical
 - Instrumentation
 - Cost-effective to complete all improvements at once
 - Single project allows for all work to be complete prior to waterfront development



Proposed Upgrade

1

Odor Control

- Install two new Odor Control Units with one unit dedicated for the Sludge Garage
- Consider activated carbon systems
- Reduce on-site odors

2

Update Process Systems

- Grit system improvements
- New Grinder
- New process piping, valves, and gates
- Updates to chemical feed system

3

Building Updates

- Upgrades to the building structure including the roof, masonry, doors, and louvers
- HVAC updates
- PLC/SCADA updates
- New electrical room
- New Generator and automatic Transfer equipment

4

Ancillary Improvements

- Cleanout and Air Release Valve replacements along force main
- Surge Tank updates
- Establish emergency bypass plan for force main and purchase response equipment

Proposed Schedule

Milestone	Date*
Begin Design	September 2021
Bid Opening	May 2022
Begin Construction	June 2022
Project Substantial Completion	April 2023
Initiation of Operation	May 2023

*Dates subject to change


Proposed Project Costs

CITY OF DOVER, NEW HAMPSHIRE W-P PROJECT NO. 20494A – RIVER STREET PUMP STATION UPGRADE CONCEPTUAL DESIGN PROJECT COST ESTIMATE, APRIL 2021		
<u>PROJECT COMPONENT</u>		<u>COST</u>
CONSTRUCTION		\$6,110,000
CONSTRUCTION CONTINGENCY	10%	\$610,000
TECHNICAL SERVICES ALLOWANCE	20%	\$1,222,000
MATERIALS TESTING	1%	\$61,000
LEGAL/ ADMINISTRATIVE	2%	\$122,000
	SUBTOTAL	\$8,125,000
FINANCING	1.0%	\$81,000
ENGINEER'S ESTIMATE OF PROJECT COST		\$8,206,000

Notes:

1) Cost estimate is based on ENR CCI 11749 (dated March 2021).

Next Steps



THANK YOU
