


Dover, New Hampshire, City Council Water System Facilities Improvements July 29, 2015



AGENDA

- System Overview
- Slide Show of Facilities (quick)
- Needed Improvements
- Approach
- Phase I Project

SYSTEM OVERVIEW

City of Dover Water System

- 28,000 people served
- 2.4 million gallons produced on average day
- 8 wells
- 3 water treatment facilities
- 2 artificial recharge facilities
- 2 water storage tanks
- 1 booster pumping station

Calderwood Well



Campbell Well



Isinglass Recharge



Hughes Well



Bouchard Well



French Cross Road WTP



Smith Well



Cummings Well



Lowell Ave. WTP



Griffin Well



Griffin WTP



Ireland Well



Bellamy Recharge



Garrison Hill Reservoir



North End Booster Pumping Station



North End Tank




NEED FOR PROJECT

Need for Project

- Some facilities over 50 years old
- NHDES Sanitary Survey deficiencies (health and safety)
 - Chemical containment
 - Eye wash and shower
 - Online water quality monitoring instruments
- Process inefficiencies (energy use, water use)
- Building inefficiencies (HVAC) and code violations

2011 Facilities Plan Summary

- Three Phases (short, intermediate, long)
- Total: \$9M
- Did not include the following major components:
 - Willand Pond Wells
 - New Pudding Hill Wells
 - Lowell Avenue WTP filtration system replacement
- A lot of new challenges have developed



● 3/4 of Production
● ● 1/4 of Production

LEGEND:

- EXISTING WATERMAIN
- MAIN PRESSURE ZONE
- NORTH END PRESSURE ZONE

3000 0 3000 6000
 SCALE: 1 INCH = 3000 FT.

DATE
 1/26/2015
 PROJECT
 1889
UNDERWOOD
 engineers
 25 Vaughan Mall, Portsmouth, N.H. 03801
 Tel. 603-436-6192 Fax. 603-431-4733

OVERVIEW
 WATER FACILITIES IMPROVEMENTS
 DOVER, NH

FIG.
 1

APPROACH

**WATER SYSTEM FACILITIES PLAN
UPDATE AND PRIORITIZATION
CITY OF DOVER, NEW HAMPSHIRE**

**FINAL
APRIL 2015**



Portsmouth and Concord, New Hampshire
FILE NO 1889

Project Priorities

- Maintain Existing Infrastructure
 - Manage supplies and facilities proactively
- Cost-Effectiveness
 - Efficient use of resources
- Keep Things in Context / Big Picture
 - Invest in most valuable supplies
 - Understand vulnerable supplies
- Develop a Specific Phased Priority Program
- Well Management Plan and Monitoring Program

Coordination With Other Projects and External Factors

- Willand Pond Wells
- New Well in Pudding Hill Aquifer
- Pudding Hill Artificial Recharge
- Ireland Well Replacement
- Barbadoes Pond water levels impacts

Table 3. Normalized Costs for all Recommended Improvements through Long-Term

Facility	Yield or Treatment Capacity (gpm)	Notes	Normalized Cost (\$/gpm)
<u>WELLS</u>			
Calderwood Well	600		\$1,800
Campbell Well	400		\$2,700
Hughes Well	350		\$9,400
Bouchard Well	600		\$100
Smith Well	600	Note 6	\$300
Cummings Well	300	Note 6	\$3,200
Griffin Well	500		\$300
Ireland Well	600		\$1,500
<u>POTENTIAL NEW SUPPLY PROJECTS - PHASE II TIMEFRAME</u>			
Willand Pond Wells	600		\$5,500
DPH-1 Well (new Griffin Well)	500	Note 5	\$3,400
<u>POSSIBLE FUTURE SUPPLIES</u>			
		Note 1	
Bedrock Well - Day Property	100	Note 2	\$28,300
Interconnect w/ Somersworth	556	Note 3	\$2,800
Bedrock Wells - Other		Note 4	
<u>TREATMENT PLANTS</u>			
French Cross Road WTP	1000	Note 7	\$37
Lowell Avenue WTP	1177		\$2,600
Griffin WTP	500		\$4,600
<u>RECHARGE FACILITIES</u>			
Isinglass Recharge	1500		\$300
Bellamy Recharge	3600		\$300

Planned Improvements through Long-Term

Flow Treatment (gpm)	Notes	Normalized Cost (\$/gpm)
600		\$1,800
400		\$2,700
350		\$9,400
600		\$100
600	Note 6	\$300
300	Note 6	\$3,200
500		\$300
600		\$1,500


PHASE II TIMEFRAME

600		\$5,500
500	Note 5	\$3,400

What this Means

- Invest appropriately or delay facilities that may not be needed or may be impacted by other projects:
 - Hughes Well: Bouchard impacts (vice-versa)
 - Pudding Hill Aquifer: New wells and Griffin WTP
- Consider future projects in current design
 - Lowell WTP: (Willand Pond wells)

City of Dover, NH Water Facilities Action Plan – Phase I



Improvements Program Summary

Phase	Cost	Schedule
I	\$7.3M	2015 to 2017
II	\$8.3M	2017 to 2020
Long-Term	\$5.4M	2025+
Total (Planning)	\$21.0M	

PHASE I

Phase I Summary

- Includes 14 sites (out of 16 total)
- All include at least short-term improvements (safety, etc.)
- 10 sites will be “done” if budget allows
 - Calderwood
 - Campbell
 - Lowell WTP
 - Smith & Cummings
 - French Cross WTP & Bouchard
 - Garrison Hill Reservoir
 - North End Tank and Booster Sta.
- Includes planning for Phase II, Energy Audit, Rates, Public Info
- Future work will be required on rest of sites

Phase I Funding

- \$6.5M DWSRF loan
 - Low interest
 - 15% principal forgiveness (\$975,000)
- Phase I estimated cost \$7.3M
 - Project to be bid with additive alternates
 - Some elements may move to Phase II

Phase I Schedule

- Design – 2015
- Bidding/Award – Spring 2016
- Substantial Completion (Wells) – Fall 2016
- Substantial Completion (Lowell WTP) – Spring 2017
- Note: Smith and Cummings Wells will be temporarily unavailable during construction of Lowell WTP.

Improvements Program Summary

Phase	Cost	Schedule
I	\$7.3M	2015 to 2017
II	\$8.3M	2017 to 2020
Long-Term	\$5.4M	2025+
Total (Planning)	\$21.0M	

Questions and Answers

