



131 Presumpscot Street
Portland, ME 04103
T: 207.874.2323
F: 207.874.2727

**15027: Dover High School and Career
Technical Center**
25 Alumni Drive
Dover, NH 03820

Change Request Proposal 190384

Title **Trough Excavation Backfill**
Date Issued **25-JUN-19**
Proposal Status **Submitted (Not Proceeding)**

Architect	Owner
Alan Pemstein HMFH Architects, Inc. 130 Bishop Allen Drive Cambridge, MA 02139 T: 617.844.2140 F: 617.876.9775 E: apemstein@hmfh.com	Robert Carrier Dover School District 61 Locust Street 409 Dover, NH 03820-4132 T: 603.516.6800 F: 603.516.6809 E:

Project Cost And Schedule Impacts

This proposal will increase the value of this contract by \$4,303.00.

Scope Of Work

Proposal to backfill the excavation area due to the removal of the troughs at the ball fields. Pricing does not include cost for contaminated soils/water or debris removal. Excavation area will be backfilled with site common fill.

Work is on hold in this area pending CO approval. Extended GCs are not included in this change order and will be negotiated and submitted separately based on other additional work that will impact final completion.

Cost Items

Description	Company	Phase	Amount
1. Backfill Excavation (SUR)	S.U.R. Construction Inc.	190384	\$ 3,966.00
2. PC Administration (5%)	PC Construction	190384	\$ 198.00
L1 Markup - Overhead & Profit (2%)		900000	\$ 83.00
L2 Markup - Insurance (0.75%)		016150	\$ 32.00
L2 Markup - P&P Bond (0.56%)		016200	\$ 24.00
Total			\$4,303.00

Architect/Engineer Recommendation

I have reviewed this change proposal and agree that it appears to be fair and reasonable and recommend acceptance.

Signature _____ Date _____

Name & Title of Authorized Representative
Alan Pemstein

HMFH Architects, Inc.


Owner Approval

By signing below, the Owner authorizes this work to proceed and agrees that PC shall be compensated by the appropriate time and cost. This Change Request Proposal will be included in the next Contract Change Order.

Signature _____ Date _____

Name & Title of Authorized Representative
Robert Carrier
Joint Building Committee Chair
Dover School District

This change request proposal includes only the direct costs associated with this work. PC Construction Company reserves the right to later claim schedule adjustment and extension of time, and for all other indirect impact costs caused by or resulting from this change proposal and cumulative effects of other change orders to the work of this contract.



S·U·R
SITES • UTILITIES • ROADS

S.U.R. Construction, Inc.

233 Chestnut Hill Road
P.O. Box 720
Rochester, NH 03866-0720

Phone: (603) 332-4554
Fax: (603) 332-0351
www.surconstruction.com

June 25, 2019
Ellen Brooks
PC Construction
131 Presumpscot St
Portland, ME 04103

Project Name: Backfill of trough excavation for oil removal at the former high school location

Project Location: High School and Technical Center, Dover, NH

- It is anticipated there is no contaminated water in the hole. All dewatering will be treated with a dirt bag only.
- The hole is 42'L x 40'W x 7'D = 436 cubic yards of backfill. This proposal is based on using on site common fill to backfill the hole.
- Any contaminated soils or demolition debris removal is excluded
- Work will be completed by crews on site. No additional mobilization has been included.

Supply and install = \$3570.00

Bond 1% - \$35.70

Mark up 10% - \$360.57

TOTAL = \$3966.27

Sincerely,



Andrew LePage



S.U.R. Construction, Inc.

